Permit No. 2023-025 Received complete: May 31, 2023

Applicant: Linda McGinty; The Luther Company, LLLP

Consultant: Steve Sabraski; Landform Professional Services, LLC

Project: Luther Bloomington Hyundai Building Additions and Site Improvements

Location: 4801 American Boulevard West, Bloomington, MN

Applicable Rules: 4, 5, 11, and 12

Reviewers: Parker Brown & Louise Heffernan; Barr Engineering Co.

## **General Background & Comments**

The applicant proposes redevelopment of the existing commercial site located at 4801 American Boulevard West in Bloomington (Luther Hyundai). Currently, the 7.3-acre site is occupied by a commercial building with surface parking. Proposed work includes the construction of three building additions along the north, northwest and southern portions of the existing structure, landscaping, bituminous and concrete improvements, utility improvements, the construction of an underground stormwater management facility, and the removal of two existing stormwater management facilities.

The site is shown in Figures 1 and 2 below.

Figure 1. Luther Hyundai Site.



Figure 2. Site within the City of Bloomington.



The district's requirements for both stormwater management and erosion and sediment control apply to the project because more than 50 cubic yards of material will be disturbed and 5,000 square feet or more of surface area is altered, Rules 4.2.1a and b and 5.2.1a and b.

One permit has previously been issued by the NMCWD for work at the Luther Hyundai site. Relevant project site information is provided in the table below.

Site Information <sup>3</sup>	Permit 2011-046	Permit 2023-025 (Current)	Site Aggregate Total (Includes 2 Projects)
Total Site Area¹ (ac)	7.29	7.29	7.29
Existing Site Impervious Area <sup>2</sup> (ac)	5.98	5.93	5.98
Change (increase or decrease) in Site Impervious Area (ac)	-0.05	0.0	-0.05
Percent Change in Impervious Area (%)	-0.8%	0%	-0.8%
Disturbed and Reconstructed Impervious Area (ac)	0.18	0.65	0.83
Percent Disturbance of Existing Impervious Area (%)	2.9%	11.0%	13.8%

<sup>&</sup>lt;sup>1</sup>Total site area includes one parcel.

<sup>&</sup>lt;sup>2</sup>Permit #2011-046 existing site impervious area includes pre-2008 project existing conditions. Activity subject to Rule 4.2.5 is considered in aggregate, and the requirements applicable to the activity will be determined with respect to all development and redevelopment that has occurred at the site since the date the rule took effect (March 2008).

<sup>&</sup>lt;sup>3</sup>The description of property information here is based on present information in NMCWD's possession. Adjustment in the context of an overall stormwater management plan for the Luther Hyundai site may be necessary, but any minor discrepancy that could be discovered through detailed analysis of the redevelopment projects undertaken in the last 15 years would not affect the outcome of the analysis of the present application.

#### Exhibits Reviewed:

- 1. Permit Application dated February 20, 2023, (received March 9, 2023).
- Stormwater Management Plan dated March 8, 2023, (received March 9, 2023), revised May 30, 2023, (received May 31, 2023), prepared by Landform Professional Services, LLC.
- 3. Geotechnical Evaluation dated June 8, 2011, (received March 9, 2023), prepared by Northern Technologies, Inc.
- 4. Electronic HydroCAD models received March 9, 2023, revised May 31, 2023, prepared by Landform Professional Services, LLC.
- 5. Electronic MIDS model files received March 9, 2023, revised May 31, 2023, prepared by Landform Professional Services, LLC.
- 6. Plans dated March 8, 2023, (received March 9, 2023) revised May 30, 2023, (received May 31, 2023) prepared by Landform Professional Services, LLC.
- 7. Soil Borings Logs dated May 1, 2023, prepared by American Engineering Testing, Inc.
- 8. Landform Professional Services, LLC Comment Responses received May 31, 2023.

The application with the submittal items above is complete.

### 4.0 Stormwater Management

NMCWD's requirements for stormwater management apply to the project because more than 50 cubic yards of material will be disturbed and 5,000 square feet or more of surface area is altered, Rules 4.2.1a and b.

The NMCWD's Rule for Redevelopment, Rule 4.2.3, states, if a proposed activity will disturb more than 50% of the existing impervious surface on the site or will increase the imperviousness of the site by more than 50%, stormwater management will apply to the entire project site. Otherwise, the stormwater requirements will apply only to the disturbed, replaced, and net additional impervious surface on the project site. Because one other project has been permitted since Rule 4.2.5 became effective in 2008 (Permit 2011-046) the proposed work under the current application (Permit 2023-025) is considered in aggregate with activities subject to Rule 4.2.5 Common Scheme of Development.

The project activities under the current application, considered in aggregate with the previous project permitted at the site, result in a 13.8% combined disturbance of the existing impervious surface, less than 50% of the existing impervious area at the site, and will not increase the imperviousness at the site by more than 50% (no combined increase). Therefore, stormwater management is required only for the net new impervious area (0 square feet) and 0.65 acres of newly disturbed and reconstructed areas under the current permit application, 28,230 square feet of regulated impervious surface.

Stormwater management for compliance with subsection 4.3.1a-c criteria will be provided by an underground stormwater management facility (UGSWMF) to provide rate control, volume retention and water quality management for the regulated areas. Two stormwater management facilities have previously been constructed at the site, including an underground

stormwater management facility located on the west and south sides of the existing structure. The two existing underground stormwater management facilities are proposed to be removed, and the stormwater management for compliance with the NMCWD rules under Permit 2011-048 and the current application will be provided by the proposed facility.

Rule 4.3.1b requires the 2-, 10-, and 100-year post development peak runoff rates be equal to or less than the existing discharge rates for all collection points where stormwater leaves the site. The applicant used a HydroCAD hydrologic model to simulate runoff rates. The existing and proposed 2-, 10- and 100-year frequency discharge rates are summarized below.

Existing Conditions				
Discharge Location	2- year (c.f.s.)	10- year (c.f.s.)	100- year (c.f.s.)	
To South	26.8	40.9	70.8	
North to American Blvd	1.2	1.9	3.6	

Proposed Conditions				
Discharge Location	2- year (c.f.s.)	10- year (c.f.s.)	100- year (c.f.s.)	
To South	24.3	37.5	70.4	
North to American Blvd	1.1	1.8	3.4	

The proposed stormwater management facility provides attenuation of the site rate(s) of runoff, resulting a reduction of peak 2-, 10, and 100-year discharges at both major discharge points. Rule 4.3.1b is met.

The Northern Technologies, Inc. geotechnical report and American Engineering Testing boring logs generally identify the underlying soil within the area of the UGSWMF as silty sand (SM), underlain by a restrictive layer(s) of clayey sand (SC). The plans must indicate that soils with low permeability in the area of the proposed facility will be excavated, removed, and backfilled with material suitable for infiltration. A design infiltration rate of 0.45 inches per hour has been used for design, using infiltration rates identified in the Minnesota Storm Water Manual for silty sands.

A retention volume of 640 cubic feet<sup>1</sup> is required from the 7,684 square feet of regulated impervious area under Permit 2011-046, based on the NMCWD rules when the previous project was permitted. A retention volume of 2,588 cubic feet is required from the newly regulated 28,230 square feet of disturbed and reconstructed impervious area under the current application. Because the two in-place UGSWMF's will be removed, the proposed facility is

<sup>&</sup>lt;sup>1</sup> Based on the NMCWD rules at the time of the permitted activities, including 1.0 inches of runoff required from the regulated areas

required to provide the required volume retention for the two projects (Permits 2011-048 and 2023-025), amounting to 3,228 cubic feet of volume retention required.

The table below summarizes the volume retention required and volume retention provided by the proposed facility. The proposed project is in conformance with subsection 4.3.1a.

## **Volume Retention Summary**

Required Volume Retention (cubic feet)	Provided Volume Retention (cubic feet)	Maximum Infiltration Depth Allowable* (feet)	Provided Infiltration Depth (feet)
3,228	3,347	4.5	2.4

<sup>\*</sup>Maximum inundation depth allowable for the UGSWMF to draw down within 48-hours based on a design infiltration rate of 0.45 inches/hour and 40% rock voids.

With an infiltration area of 2,087 square feet to be provided (1,793 square feet required), the required volume retention is drawn down within the required 48-hours, complying with Rule 4.3.1a (ii).

Rule 4.5.4d (i) requires three feet of separation between the bottom of an infiltration facility and groundwater. No groundwater was encountered in soil borings near the proposed infiltration facility. The Northern Technologies, Inc. boring located near the proposed facility did not encounter groundwater to the bottom of the boring, approximately elevation 819 M.S.L. The bottom of the proposed facility is elevation 830.5 M.S.L., approximately 11.5 feet above the elevation where groundwater was not encountered in SB-1. Rule 4.5.4d (i) is met.

NMCWD's water quality criterion requires 60% annual removal efficiency for total phosphorus (TP) and 90% annual removal efficiency for total suspended solids (TSS) from the regulated site runoff. The results from the MIDS model provided show the UGSWMF will provide the required annual removal efficiency. The results of the MIDS modeling are summarized in the table below. We agree with the modeling results and the project is in conformance with Rule 4.3.1c criteria.

### **Annual TSS and TP Removal Summary**

Pollutant of Interest	Regulated Site Loading (lbs./year)	Required Load Removal (lbs./year)	Provided Load Reduction (lbs./year)
Total Suspended Solids (TSS)	250	225 (90%)	230 (92%)
Total Phosphorus (TP)	1.4	0.8 (60%)	1.3 (92%)

Rule 4.3.3 states that all new and reconstructed buildings must be constructed such that the low floor is at least two feet above the 100-year high-water elevation or one foot above the emergency overflow of a constructed facility. Additionally, Rule 4.3.3 also states that a stormwater management facility must be constructed at an elevation that ensures no adjacent habitable building will be brought into noncompliance with a standard in subsection 4.3.3.

The low floor elevations of the existing structure(s) in relation to the proposed UGSWMF's 100-year high-water elevation is summarized in the table below, in compliance with subsection 4.3.3 criteria.

#### **Low Floor Elevation Summary**

Low Floor Elevation of Existing Structure(s) (M.S.L.)	100-year Frequency Flood Elevation of Proposed Facility (M.S.L.)	Low Floor Elevation Freeboard (feet)
839.5	835.8	3.7

Rule 4.3.3 also states that all new and reconstructed buildings must be constructed such that no opening where surface flow can enter the structure is less than two feet above the 100-year high-water elevation of an adjacent facility. The low opening floor elevation(s) of the proposed additions and existing structure must be identified for compliance with subsection 4.3.3 criteria.

In accordance with Rule 4.3.1a (i), where infiltration or filtration facilities, practices or systems are proposed, pre-treatment of runoff must be provided. Sump manholes will provide the required pretreatment of runoff prior to discharging to the UGSWMF, complying with Rule 4.3.1a (i).

In accordance with Rule 4.3.4, a post-project chloride management plan must be provided that will, 1) designate an individual authorized to implement the chloride-use plan and 2) designate a MPCA certified salt applicator engaged in the implementation of the chloride-use plan for the site.

Subsection 4.3.5 requires the submission of a maintenance plan. All stormwater management structures and facilities must be designed for maintenance access and properly maintained in perpetuity to assure that they continue to function as designed. The applicant must provide a receipt showing recordation of a maintenance declaration for the operation and maintenance of the stormwater management facility, including the sump manholes to be provided.

## 5.0 Erosion and Sediment Control

NMCWD's requirements for erosion and sediment control apply to the project because more than 50 cubic yards of material will be disturbed and 5,000 square feet or more of surface area is altered, Rules 5.2.1a and b.

The erosion control plan prepared by Landform Professional Services, LLC includes installation of perimeter control (bio rolls) at the limits of construction, a stabilized rock construction entrance and storm sewer inlet protection.

The contractor for the project will need to designate a contact who will remain liable to the district for performance under NMCWD's Erosion and Sediment Control Rule 5.0 from the time the permitted activities commence until areas disturbed are restored, in accordance with subsection 5.4.1e. NMCWD must be notified if the responsible individual changes during the permit term.

### **11.0 Fees**

Fees for the project are:

Rules 4.0 and 5.0\$2	2,00	)0	)
----------------------	------	----	---

#### 12.0 Financial Assurances

Financial Assurances for the project are:

Rule 4: Stormwater Management Facility: 1,793 S.F. x \$12/S.F.=	\$21,516
Rule 5: Perimeter Control: 591 L.F. x \$2.50/L.F. =	\$1,478
Inlet Protection: 7 x \$100 =	\$700
Site Restoration: 2.2 acres x \$2,500/acre =	\$5,500
Chloride Management	\$5,000
Contingency and Administration	\$12,506

## **Findings**

- 1. The proposed project includes the information necessary, plan sheets and erosion control plan for review.
- 2. The proposed project will conform to Rules 4.0 and 5.0 requirements with the fulfilment of the conditions identified in the *Recommendations* section of this report.
- 3. The proposed stormwater management facility will provide volume retention, rate control and water quality management in accordance with subsections 4.3.1a-c criteria.
- 4. In accordance with NMCWD Rule 4.3.5, the applicant must provide a maintenance and inspection plan that identifies and protects the design, capacity, and functionality of the stormwater management facility and the sump manholes constructed by the project.

#### Recommendation

Approval, contingent upon:

Compliance with the General Provisions (attached).

Financial Assurance in the amount of \$46,700, \$41,700 for stormwater management, erosion control and site restoration, and \$5,000 for compliance with the chloride management requirements.

The applicant provides a name and contact information for the individual responsible for the erosion and sediment control at the site. NMCWD must be notified if the responsible individual changes during the permit term.

A design infiltration rate of 0.45 inches per hour has been used for design, using infiltration rates identified in the Minnesota Storm Water Manual for silty sands. The plans must indicate that soils with low permeability encountered in the area of the proposed facility will be excavated, removed, and backfilled with material suitable for infiltration.

Per Rule 4.3.5, a receipt showing recordation of a maintenance declaration for the operation and maintenance of the stormwater management facility and stormwater infrastructure. A draft of the declaration must be approved by the district prior to recordation.

Rule 4.3.3 states that all new and reconstructed buildings must be constructed such that the low floor is at least two feet above the 100-year high-water elevation or one foot above the emergency overflow of a constructed facility. To fully comply with Rule 4.3.3 criteria the following is required.

- 1. The Landform comment responses indicate that the low floor elevation of the existing building is 839.5 ft, in compliance with subsection 4.3.3 freeboard requirements. It must be clarified if the 839.5 ft low floor elevation of the existing building is also the low floor elevation for the three proposed building additions. Alternately, if the low floor elevations of the three proposed building additions differs, the elevations must be provided and comply with subsection 4.3.3 criteria, or Appendix 4a may be used to demonstrate compliance.
- 2. Rule 4.3.3 also states that all new and reconstructed buildings must be constructed such that no opening where surface flow can enter the structure is less than two feet above the 100-year high-water elevation of an adjacent facility. The Landform comment responses do not identify the low opening elevations. The low opening elevation(s) of the existing structure and the three building additions must be identified to fully comply with subsection 4.3.3 criteria.


By accepting the permit, when issued, the applicant agrees to the following stipulations for closeout of the permit and release of the financial assurance after the project:

The work for Luther Bloomington Hyundai under the terms of Permit 2023-025 must have an impervious surface area and configuration materially consistent with the approved plans. Design that differs materially from the approved plans (e.g., in terms of the total impervious area or stormwater management design) will need to be the subject of a request for a permit modification or new permit, which will be subject to review for compliance with all applicable regulatory requirements.

Per Rule 4.5.6, an as-built drawing of the underground stormwater management facility conforming to the design specifications, including a stage volume relationship in tabular form for the underground stormwater management facility, as approved by the district, must be provided. The as-built drawing must include relevant design information based on surveyed data including but not limited to the invert elevation of the pipe, the controlling outlet elevation, the bottom of the facility, etc.


Submission of a plan for post-project management of Chloride use on the site. The plan must include 1) the designation of an individual authorized to implement the chloride use plan and 2) the designation of a Minnesota Pollution Control Agency certified salt applicator engaged in the implementation of the chloride-use plan for the site. The release of the \$5,000 of the financial assurance required for the chloride-management plan requires that chloride-management plan has been provided and approved by the District's Administrator.


Rule 12.4.1b requires demonstration and confirmation that the stormwater management facility has been constructed or installed and is functioning as designed and permitted. Verification, through daily observation logs and photographs, must be provided showing the stormwater facility used for volume retention has drawn down within 48 hours from the completion of two 1-inch (approximate) separate rainfall events.





# LUTHER HYUNDAI

BLOOMINGTON, MINNESOTA









**CERTIFICATIONS** 

DATE: 05/30/2023

DATE: 05/30/2023

I HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION, OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT

SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF

I HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION, OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT

SUPERVISION AND THAT I AM A DULY LICENSED LANDSCAPE ARCHITECT UNDER THE LAWS OF THE STATE OF MINNESOTA

MINNESOTA. THIS CERTIFICATION IS FOR SHEET NUMBERS BEGINNING WITH "C".

THIS CERTIFICATION IS FOR SHEET NUMBERS BEGINNING WITH "L".

STEVE SABRASKI, P.E.

LICENSE NUMBER: 47165

LICENSE NUMBER: 44803



THE LUTHER COMPANY, LLLP 3701 ALABAMA AVENUE SOUTH ST. LOUIS PARK, MN TEL (952)258-8800 - FAX (952) 258-8900



LUTHER **HYUNDAI** BLOOMINGTON, MN


CERTIFICATION

CITY / WATERSHED RESUBMITTAL

Minneapolis, MN 55401 Web: landform.net PROJECT NO.

CIVIL & LANDSCAPE





## **GENERAL NOTES**

# 1. For construction staking and surveying services contact Landform at 612.252.9070.

## SITE PLAN NOTES

- 2. Obtain all necessary permits for construction within, or use of, public right-of-way.
- 3. The digital file, which can be obtained from the Engineer, shall be used for staking. Discrepancies between the drawings and the digital file shall be reported to the Engineer. The building footprint, as shown on these drawings, and the digital file, shall be compared to the structural drawings prior to staking.
- Reserved.
- 5. Dimensions shown are to face of curb and exterior face of building unless noted otherwise.
- 6. Delineate parking stalls with a 4-inch wide white painted stripe. Delineate access aisles with 4-inch wide white painted stripes 18 inches on center and at 45 degree angle to direction of travel.
- 7. Trash Enclosure. Refer to Architectural plans for details.
- 8. Reinstall salvaged fence. 9. Reinstall salvaged light pole.
- 10. 4-space Bike rack. See sheet L2.1 for detail.

## PROPOSED ZONING AND SETBACK SUMMARY

The Existing Property is Currently Zoned: Commercial Service (CS-0.5) Proposed Zoning: Freeway Office and Service (C-1)

Building Setback Information is as follows:

Front Yard = 35 ft.

Rear = 30 ft. Side = 20 ft.

Parking Setback Information is as follows: Front Yard = 20 ft. Rear = 5 ft. Side (interior) = 5 ft. Side (street) = 20 ft

Side (street) = 20 ft.					
	Α	REA SUM	MARY		
Existing:					
Pervious	58,149	s.f.	1.33	ac.	18
Impervious	259,620	s.f.	5.96	ac.	81
Total	317,769	s.f.	7.29	ac.	100
Proposed:					
Pervious	56,960	s.f.	1.31	ac.	17

Building expansion: 42,969 s.f. 9,210 s.f. 52,179 s.f

	PARKING SUMMARY	1	
Required Parking:			
Service Area	Three stalls for each enclosed "major service" bay	24	7:
	Two stalls for each enclosed "minor service" bay	27	54
	One stall per 300 SF of GFA excluding service bays	9,070 SF Service Area	30
Car Wash	One stall per 375 SF of GFA	776 SF Car Wash	2
Office	One stall per 285 SF of office GFA	8,834 SF Office Area	31
Large Item Retail	One stall per 180 SF of retail GFA	3,208 SF Showroom Area	18
Warehouse	One stall per 1,000 SF of warehouse GFA	7,292 sf Warehouse Area	7
Total Parking Stalls Requ	uired		214
Provided Parking:			
Inventory Stalls Customer / Employee / S Accessible Stalls Compact Stalls	(9x18) ervice stalls (9x18) (9x18) (9x16)	288 ea. 203 ea. 7 ea. 4 ea.	
Total Parking Stalls Provi	ided	502 ea.	

# LEGEND

Green Space (Landscape Area)

Customer / Employee / Service parking (remainder of stalls are sales / inventory)

I hereby certify that this plan was prepared by me, or under my direct supervision, and that I am

CERTIFICATION

DEVELOPER

THE LUTHER COMPANY, LLLP 3701 ALABAMA AVENUE SOUTH ST. LOUIS PARK, MN

TEL (952)258-8800 - FAX (952) 258-8900

**MUNICIPALITY** 

BLOOMINGTON

**PROJECT** 

LUTHER

HYUNDAI

BLOOMINGTON, MN

ISSUE / REVISION HISTORY

DRC SUBMITTAL CITY SUBMITTAL PERMIT SET CITY / WATERSHED RESUBMITTAL

15 NOV 2022 11 JAN 2023 08 MAR 2023 30 MAY 2023

82.1% 100.0%

> Steven E. Sabraski License No. 47165 Signature shown is a digital reproduction of original. Wet signed copy of this plan on file at Landform Professional Services, LLC office and is available upon request.

IF THE SIGNATURE, SEAL OR FOUR LINES DIRECTLY ABOVE ARE NOT

VISIBLE, THIS SHEET HAS BEEN REPRODUCED BEYOND INTENDED READABILITY AND IS NO LONGER A VALID DOCUMENT. PLEASE CONTACT THE ENGINEER TO REQUEST ADDITIONAL DOCUMENTS. CITY / WATERSHED RESUBMITTA




105 South Fifth Avenue Tel: 612-252-9070

Minneapolis, MN 55401 Web: landform.net FILE NAME PROJECT NO.

C201LUT22054.DWG

 $Land form @and Site \ to \ Finish @are \ registered \ service \ marks \ of \ Land form \ Professional \ Services, \ LLC.$ 





## **GENERAL NOTES**

1. For construction staking and surveying services contact Landform at 612.252.9070.

Install perimeter sediment controls prior to beginning work and maintain for duration of construction. Remove controls after areas contributing runoff are permanently stabilized and dispose of off site.

**EROSION PREVENTION AND SEDIMENT CONTROL NOTES** 

3 Install inlet protection: Wimco RD or CG models as appropriate, or approved equal. Maintain protection until project is stabilized.

4. Limit soil disturbance to the grading limits shown. Schedule operations to minimize length of exposure of disturbed areas.

Management practices shown are the minimum requirement. Install and maintain additional controls as work proceeds to prevent erosion and control sediment carried by wind or water.

Dewatering activity must ensure discharge does not adversely affect surface waters or downstream properties.

7. Soil stockpiles require perimeter control or other erosion control BMP.

Stabilization must be started immediately to limit soil erosion when the construction activity in that portion of the site has temporarily or permanently ceased and will not resume for 14 calendar days.

Contractor shall prevent sediment laden water from entering the infiltration system and all storm sewer until the site is completely

10. Seed, Sod, Mulch, Erosion Control Blanket, and Fertilizer shall meet the following Specifications, as modified. Specification Number MNDOT 3878

MN Type 21-111 @ 100 lb./ac. - Temporary Erosion Control - Temporary Erosion Control, May 1 - Jul 31 MN Type 21-112 @ 100 lb./ac. - Temporary Erosion Control - Temporary Erosion Control, Aug 1 - Oct 31

MN Type 25-151 @ 120 lb./ac. - Permanent Turf

(MNDOT Type 1 @ 2 ton/ac., Disc Anchored) Erosion Control Blanket MNDOT Type 3N

11. See Landscape Sheets for permanent turf and landscape establishment. Scrape adjacent streets clean daily and sweep clean weekly.

General Placement

## GRADING NOTES

- 13. Contact utility service providers for field location of services 72 hours prior to beginning grading.
- 14. Refer to the Geotechnical Report prepared by NTI, Dated 09/08/2011, for additional information on backfill material and groundwater
- 15. Remove topsoil from grading areas and stockpile sufficient quantity for reuse. Materials may be mined from landscape areas for use on site and replaced with excess organic material with prior Owner approval.
- 16. Remove surface and ground water from excavations. Provide initial lifts of stable foundation material if exposed soils are wet and
- 17. Rough grade Building Pad to 12 Inches below Finished Floor Elevation (FFE).
- 18. Refer to Structural Specifications for earthwork requirements for building pads.
- 19. An Independent Testing Firm shall verify the removal of organic and unsuitable soils, soil correction, and compaction and provide periodic reports to the Owner.
- 20. Place and compact fill using lift thicknesses matched to soil type and compaction equipment to obtain specified compaction
- 21. Compact cohesive soils in paved areas to 95% of maximum dry density, Standard Proctor (ASTM D698) except the top 3 feet which shall be compacted to 100%. Compact to 98% density where fill depth exceeds 10 feet. The soils shall be within 3% of optimum moisture content. In granular soils all portions of the embankment shall be compacted to not less than 95% of Modified Proctor
- 22. Coordinate with Architectural for building stoop locations. Slopes shown on adjacent walks and pavements should continue over

**INFILTRATION BASIN INFORMATION & TESTING** 

# 23. Avoid soil compaction of infiltration practices. Any equipment used in infiltration areas should be small scaled and tracked. Install

- protective fencing as shown before work begins.
- 25. DESIGN PERMEABILITY RATES:
- Infiltration Basin was designed with a permeability of 0.06 inches/hour.

TESTING:

a. Infiltration Basins: Once filtration basin media has been placed, permeability testing shall be performed.

- b. Contractor shall engage a qualified testing firm to measure the permeability of the basin surface utilizing a Double Ring Infiltrometer, Modified Philip Dunn (MPD) Infiltrometer, or other method approved by the Civil Engineer or Geotechnical Engineer. Test results shall be greater than or equal to the following rates to meet long term rates required for design: Infiltration Basin needs a permeability of 0.12 inches/hour.
- c. Contractor to contact the following to schedule testing. Representative staff from each entity may wish to observe the tests. Contact shall be made 72 hours prior to testing.
- 26. Civil Engineer: Steve Sabraski, ssabraski@landform.net, 612-252-9070 Geotechnical Engineer: TBD Nine Mile Creek Watershed: TBD

City of Bloomington: TBD 27. RATE OF TESTING: Contractor shall coordinate with the testing firm to provide permeameter tests at the following rates:

Basin Area (s.f.) No. of Tests Required Infiltration Basin I.D.

28. Test results shall be provided to the Civil Engineer, Geotechnical Engineer, Watershed, & City staff.

# **PAVING NOTES**

- 29. Spot Elevations at curblines indicate flowlines unless noted otherwise. See Sheet C4.1 for rim elevations of catch basins.
- 30. Grades between proposed spot elevations shall be continuous and nonvariable. Spot Elevations shall govern over contour lines. 31. Meet and Match existing curb. Transition as needed. 32. Paving Sections (Refer to Geotechnical Report by NTI, Dated 06-08-2011)

a. Bituminous Paving (Light Duty)
Bituminous Wear (MNDOT 2360)

Tack Coat (MNDOT 2357) Bituminous Base (MNDOT 2360) Aggregate Base (MNDOT 3138, Class 5) Compacted Subsoil

b. Bituminous Paving (Heavy Duty) Bituminous Wear (MNDOT 2360) Tack Coat (MNDOT 2357) Bituminous Base (MNDOT 2360) Aggregate Base (MNDOT 3138, Class 5) Compacted Subsoil

c. Concrete Walkways 4-inch Concrete Walk, 4000 PSI, 5%-8% Air Entrained, Max. 4" Slump (MNDOT 2301) 4-inch Aggregate Base (MNDOT 3138, CLASS 5) Compacted Subsoil

d. Concrete Drives, Aprons, and Exterior Slabs Concrete, 4000 PSI, 5%-8% Air Entrained, Max. 4" Slump (MNDOT 2301) Aggregate Base (MNDOT 3138, CLASS 5) Compacted Subsoil

Concrete Joints Install joints as shown and align across sidewalks, curbs, and pavement, paying attention to spacing of expansion joints. Joint spacing shall be as follows: a. Tooled joints: Divide panels into nominally equal areas unless shown otherwise. b. Expansion Joints: Sidewalks - 40 feet max.; Curbs - 60 feet max.; Pavement: 80 feet max.; Adjacent to building foundations and stoops.

c. Contraction Joints: Sidewalks - 8 to 10 feet; Curbs and Aprons - 12 to 15 feet. 34. Accessible Parking Stalls and adjacent access aisles shall not exceed a 2.00% slope in any direction.

35. Accessible Routes shall have a maximum cross slope of 2.00% and a maximum running slope of 5.00%.

36. Adjust all structure rims to match pavement elevations.


37. Transition from 4" concrete curb & gutter to Ribbon Curb. Refer to detail C7.1/10. 38. Contractor shall obtain a Public Works permit for obstructions and concrete work within the right-of-way. Permit is required prior to

removals or installation. Contact Sean Jenkins (952-563-4545, sjenkins@BloomingtonMN.gov) for permit information. 39. Street lighting and interconnect conduit must be exposed for city inspection prior to pouring concrete or backfilling excavation in city

SYMBOL	DESCRIPTION	ESTIMATED QUANTITY
0	:Inlet Protection	7 ea.
<del>,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,</del>	:Compost or Bio Log	591 ft.
	:Vehicle Tracking Pad	1 ea.

<del>,</del> ,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	:Compost or Bio Log	591 ft.
05050505	:Vehicle Tracking Pad	1 ea.
	:Tip Out Curb	
	:Pavement Sawcut	
	:Construction Limits	
	:Erosion Control Blanket	325 sf.





**DEVELOPER** 

3701 ALABAMA AVENUE SOUTH ST. LOUIS PARK, MN

TEL (952)258-8800 - FAX (952) 258-8900

**MUNICIPALITY** 

BLOOMINGTON

LUTHER

BLOOMINGTON, MN

DRC SUBMITTAL CITY SUBMITTAL PERMIT SET CITY / WATERSHED RESUBMITTAL

15 NOV 2022 11 JAN 2023 08 MAR 2023 30 MAY 2023

CERTIFICATION

I hereby certify that this plan was prepared by me, or under my direct supervision, and that I am

Signature shown is a digital reproduction of original. Wet signed copy of this plan on file at Landform Professional Services, LLC office and is available upon request.

VISIBLE, THIS SHEET HAS BEEN REPRODUCED BEYOND INTENDED READABILITY AND IS NO LONGER A VALID DOCUMENT. PLEASE CONTACT THE ENGINEER TO REQUEST ADDITIONAL DOCUMENTS.

IF THE SIGNATURE, SEAL OR FOUR LINES DIRECTLY ABOVE ARE NOT

CITY / WATERSHED RESUBMITT.

105 South Fifth Avenue Tel: 612-252-9070 Minneapolis, MN 55401 Web: landform.net PROJECT NO.

GRADING, DRAINAGE, PAVING, & EROSION CONTROL

Land form @ and Site to Finish @ are registered service marks of Land form Professional Services, LLC.

## NPDES PERMIT AND SWPPP COMPONENTS

1. The current Minnesota Construction Stormwater General Permit (Permit) dated August 1, 2018 is referenced in this document as the Permit.

## The SWPPP includes the following components:

- Stormwater Management Plan prepared by Landform Maintenance Plan for permanent stormwater BMPs
- Geotechnical Report prepared by NTI
- All components must be kept onsite by the Operator. The Operator shall contact Civil Engineer if they do not have all of the

## SITE INFORMATION

Site location: Latitude: 44.85714, Longitude: -93.34162

Disturbed area = 2.16 ac.

Pre-construction impervious area within disturbed area = 1.97 ac. Post-construction impervious area within disturbed area = 2.00 ac. Net change in impervious area within disturbed area = 0.03 ac.

Type of stormwater management:

Erosion prevention and sediment control quantities are on sheets C3.1

## SITE EVALUATION / ASSESSMENT / PLANNING

- 1. The Operator shall have primary responsibility and significant authority for the development, implementation, maintenance, inspection
- and amendments to the approved SWPPP. Duties include but are not limited to: Ensuring full compliance with the SWPPP and the Permit
- Implementing all elements of the SWPPP, including but not limited to:
- Implementing prompt and effective erosion and sediment control measures
- •• Implementing all non-storm water management, and good housekeeping BMPs ensuring that no materials other than Storm water are discharged in quantities, which will have an adverse effect on receiving waters or storm drain systems,
- Conducting routine inspections and maintenance
- Ensuring elimination of all unauthorized discharges · Coordinating to ensure all of the necessary corrections / repairs are made immediately, and that the project complies with the SWPPP, the Permit, and approved plans at all times.

# STORMWATER POLLUTION PREVENTION MANAGEMENT MEASURES

- . Operator must develop pollution prevention management measures, implement good housekeeping BMPs, must follow all applicable federal, state, and local building codes, Occupational Safety and Health Act (OSHA), and the general conditions and general requirements of the construction contract.
- 2. The Operator shall minimize the exposure to stormwater of any of the products, material, or wastes stored on site that may wash downstream or contaminate stormwater.
- 3. Building products that have the potential to leach pollutants must be under cover.
- 4. Chemicals and landscape materials shall be under cover to prevent the discharge of pollutants.
- 5. Operator to track progress of the following items on site maps: portable toilets, material storage areas, vehicle and equipment fueling and maintenance areas, concrete washouts, paint and stucco washouts, dumpsters or other trash and debris containers, spill kits, stockpiles, any other non-structural non-storm water management BMPs, any temporarily removed structural BMPs, any changes to the structural BMPs.
- 6. Solid waste: collected sediment, asphalt and concrete millings, floating debris, paper, plastic, fabric, construction and demolition debris and other wastes must be disposed of properly and must comply with MPCA disposal requirements.
- 7. Hazardous waste: oil, gasoline, paint and any hazardous substances must be properly stored in sealed containers to prevent spills, leaks or other discharge. Restricted access to storage areas must be provided to prevent vandalism. Storage and disposal of hazardous waste or materials must be in compliance with Minn. R. Ch. 7045 including secondary containment as applicable.
- 8. Portable toilets must be positioned so that they are secure and will not be tipped or knocked over.
- 9. Concrete and other washout waste: operator must provide effective containment for all liquid and solid wastes generated by washout operations. The liquid and solid wastes must not contact the ground, and the containment must be designed so that it does not result in runoff from the washout operations or areas. Liquid and solid wastes must be disposed of properly and in compliance with MPCA rules. A sign must be installed adjacent to each washout facility that requires site personnel to utilize the proper facilities for disposal of concrete and other washout wastes.
- 10. External vehicle washing: external washing of trucks and other construction vehicles must be limited to a defined area of the site. Runoff must be contained and waste properly disposed of. No engine degreasing is allowed on site.
- 11. Operator shall take reasonable steps to prevent the discharge of spilled or leaked chemicals, including fuel, from any area where they will be loaded or unloaded as detailed in the Permit.

## SWPPP CONTACT AND TRAINING INFORMATION

The Luther Company, LLLP attn: Linda McGinty 3701 Alabama Avenue S St. Louis Park, MN 55416

(952) 258-8800

- To Be Determined. Contact Owner until Contractor Is Selected.
- 3. Long Term Maintenance And Operation: To Be Determined. Contact Owner until Contractor Is Selected.
- 4. SWPPP Designer: Steve Sabraski, P.E. Landform Professional Services
- Certification: U Of MN, Design Of Construction SWPPP, Exp. May 31, 2025
- SWPPP Inspector / Manager: To Be Determined. Contact Owner until Contractor And SWPPP Inspector / Manager is selected.

To Be Determined. Contact Owner until BMP Installer And Maintainer is selected.

# Minneapolis, Mn 55401

BMP Installation And Repair:

- 105 South Fifth Avenue, Suite 513 612-252-9070 ssabraski@landform.net

## DESCRIPTION OF CONSTRUCTION ACTIVITY

1. Construction activity includes erosion and sediment control BMPs installation, clearing and grubbing, site grading, utility installation, building construction, paving, and landscaping.


# SCHEDULE OF BMP INSTALLATION AND CONSTRUCTION ACTIVITY

- Install perimeter sediment control BMPs prior to start of other site work. Refer to Grading, Drainage, Paving and Erosion Control sheet for initial locations of BMPs.
- Protect infiltration areas with construction fencing. Install fencing prior to site grading or within 24-hours of excavating an infiltration
- Construct temporary / permanent sedimentation basins prior to upland disturbance. Install perimeter sediment control BMPs around
- normal water levels within 48-hours of completion of basin grading. Stabilize outlets from temporary / permanent sedimentation basins within 24-hours of outlet construction.

5. Perform work in phases to minimize disturbed area at any one time. Operator to develop phasing plan prior to start of work.

- Strip topsoil from areas to be disturbed and stockpile with perimeter sediment control BMPs. Provide stabilization if stockpile is left longer than 14 days
- Rough grade site. Install utilities.
- 9. Install small utilities (gas, electric, communications).
- 10. Final grade pavement areas and compact subgrade.
- 11. Lay down pavement aggregate and compact.
- 12. Install curb and gutter. Backfill after a minimum of three days and provide a minimum of two rolls of sod at the back of curb.
- 13. Construct building / addition and site features.
- Construct site walks and patios.
- Provide final stabilization. 16. Connect infiltration / filtration practices to storm sewer inlets.
- 17. Remove temporary BMPs and dispose of properly.

## WATERS WITHIN ONE MILE OF SITE



## MN SPECIAL (PROHIBITED, RESTRICTED, OTHER) & IMPAIRED WATERS Lake Edina is impaired based on the current USEPA 303(d) clean water act list; is within 1 mile of this site; and stormwater does not

discharge to it. Impairments are for Aquatic consumption. Nine Mile Creek is impaired based on the current USEPA 303(d) clean water act list; is within 1 mile of this site; and stormwater does not discharge to it. Impairments are for Aquatic Life.

## EROSION PREVENTION AND SEDIMENT CONTROL

1. See Grading, Drainage, Paving and Erosion Control sheets for the location and type of temporary erosion prevention and sediment control BMPs. See Grading and Drainage, Utility, and Landscape sheets for the location and type of permanent erosion prevention and sediment control BMPs.

## Minimize Disturbed Areas and Protect Natural Features and Soil

Appropriate construction practices (e.g. construction phasing, vegetative buffer strips, horizontal slope grading) shall be used to minimize erosion.

Areas not to be disturbed (buffers, infiltration basins, etc.) shall be protected with construction or silt fence before work begins. Operator shall develop methods to minimize soil compaction outside of building pads, pavement areas and utility trenches and shall use tracked equipment wherever practicable. Topsoil shall be salvaged and reused to the extent practicable.

## Phase Construction Activity

## Operator must not disturb more land than can be effectively inspected and maintained.

Sediment control practices shall be established on all down gradient perimeters before any upgradient land disturbing activities begin. These practices shall remain in place until final stabilization has been established in accordance with the Permit. The timing of the installation of sediment control practices may be adjusted to accommodate short-term activities such as clearing or

grubbing, or passage of vehicles. Any short-term activity must be completed as quickly as possible and the sediment control

practices shall be installed immediately after the activity is completed. However, sediment control practices shall be installed before

# Control Stormwater Flowing onto and Through the Project

the next precipitation event even if the activity is not complete.

The normal wetted perimeter of any temporary or permanent drainage ditch or swale that drains water from any portion of the construction site, or diverts water around the site, shall be stabilized within 200 lineal feet from the property edge, or from the point of discharge into any surface water.

connecting to a surface water and construction in that portion of the ditch has temporarily or permanently ceased.

Stabilization of the last 200 lineal feet shall be completed within 24 hours after connecting to a surface water. Stabilization of the remaining portions of any temporary or permanent ditches or swales shall be complete within 14 days after

Temporary or permanent ditches or swales that are being used as a sediment containment system (with properly designed rock ditch checks, bio rolls, silt dikes etc.) do not need to be stabilized. These areas shall be stabilized within 24 hours after no longer being used as a sediment containment system.

## . Stabilize Soils

All exposed soil areas, including stockpiles, must be stabilized.

Stabilization must be started immediately to limit soil erosion when the construction activity in that portion of the site has temporarily or permanently ceased and will not resume for 14 calendar days. Stabilization must be complete within 14 days of cessation of construction activity.

Temporary soil stockpiles shall have silt fence or other effective sediment controls, and cannot be placed in surface waters, including storm water conveyances such as curb and gutter systems, or conduits and ditches unless there is a bypass in place for the storm

Temporary stockpiles without significant silt, clay or organic components (e.g. clean aggregate stockpiles, demolition concrete stockpiles, sand stockpiles) and the constructed base components of roads, parking lots and similar surfaces, are exempt from this

- Protect Slopes Operator shall avoid work on slopes with a grade of 3:1 or greater when practicable. Grading on slopes with a grade of 3:1 or steeper will require techniques such as phasing and stabilization practices designed for steep slopes(e.g. slope draining and terracing).
- . Protect Storm Drain Inlets
- All storm drain inlets shall be protected by appropriate BMPs during construction until all sources with potential for discharging to the inlet have been stabilized. Inlet protection may be temporarily removed if a specific safety concern has been identified.
- 8. Provide Energy Dissipation at all Pipe Outlets within 24 Hours

After connection to a surface water or permanent stormwater treatment system.

Refer to Permit requirements for temporary or permanent sediment basins.

- 9. <u>Establish Perimeter Controls and Sediment Barriers</u>
- Prior to disturbing soils on a project site, establish sediment control BMPs on all down-gradient perimeters and where site discharges to public waters.
- 10. Retain Sediment On-site and Control Dewatering Practices

Discharge shall not cause nuisance conditions, erosion in receiving channels, adversely affect receiving water or impact wetlands, or downstream properties. Discharge points shall be adequately protected from erosion and scour by accepted energy dissipation

Discharge water containing oil or grease shall be treated to remove oil or grease prior to discharge to surface waters.

## 11. <u>Establish Stabilized Construction Exits</u>

Vehicle tracking pads shall be established as shown on the Grading, Drainage, Paving and Erosion Control sheet to minimize tracking of sediment from the construction site onto adjacent streets.

# 12. <u>Infiltration Basin Protection</u>

Operator must not excavate infiltration systems to final grade or within three (3) feet of final grade until the contributing drainage area has been constructed and fully stabilized unless rigorous erosion prevention and sediment controls have been installed. When excavating an infiltration system to within three (3) feet of final grade, operator shall mark off and protect the area from heavy construction equipment to prevent compaction of soils.

## 13. <u>Dewatering and Basin Draining</u>

Permittees must discharge turbid or sediment-laden waters related to dewatering or basin draining to a temporary or permanent sediment basin. Discharges must not cause erosion or scour near the discharge points.

# 14. Remove Sediment from Surface Waters

All sediment deposits and deltas must be removed from surface waters, including drainage ways, catch basins, and other drainage systems, and the removal areas restabilized within seven (7) days.

## TEMPORARY SEDIMENTATION BASIN(S)

- 1. This project does not have more than five (5) disturbed acres draining to a common location and the site does not drain to an impaired or special water, therefore a temporary sediment basin is not required.
- 2. Temporary sediment basins shall provide treatment to runoff before it leaves the construction site or enters surface waters. The contractor shall comply with the following requirements: A. Sedimentation basins must provide live storage of runoff resulting from the 2-year 24-hour rainfall event from each acre drained to the basin, with a minimum of 1,800 c.f./acre live storage volume. (Where no calculation has been performed, each
  - basin shall provide at least 3,600 c.f./acre live storage.) Sedimentation basins must include a stabilized emergency overflow to prevent basin integrity failure. B. Discharge from temporary sedimentation basins will be withdrawn from the surface in order to minimize the discharge of
- 3. Discharge from basin draining shall not adversely affect the receiving water or downstream properties. Contractor will visually check
- to ensure adequate treatment has been obtained and that nuisance conditions will not result from the discharge.

- 4. Any discharge observed to be occurring during the inspection shall be recorded, described, and photographed.

- 5. If any proposed temporary BMPs are not working as intended refer to the "Stormwater Compliance Assistance Toolkit for Small
- Construction Operators", MPCA, 2017 for additional information. Operator shall contact the SWPPP Designer for additional

# POST CONSTRUCTION / PERMANENT BMPS

1. See Grading and Drainage, Utility, and Landscape sheets for post construction and permanent stormwater BMPs.

# INSPECTIONS AND MAINTENANCE

- 1. Permittees must ensure that a trained person will inspect the entire construction site at least once every seven (7) days during active construction and within 24 hours after a rainfall event greater than 0.5-inches in 24 hours.
- 2. Inspections shall include stabilized areas, erosion prevention and sediment control BMPs, and infiltration areas.

3. Surface waters on or adjacent to the site must be inspected for evidence of erosion or sediment deposition.

- 4. Permittees must record all inspection and maintenance activities within 24 hours of being conducted as detailed in the Permit.
- Inspection Records content shall include: Date and time of inspections;

requirements and information.

- Name of persons conduction inspections;
- Findings of inspections, including specific locations where corrective actions are needed; Corrective actions taken including dates, times, and the party taking the corrective action;
- Dates of all rainfall events greater than 1/2 inch in 24 hours (refer to Permit for measurement requirements); Any discovered discharge must be recorded, including photographs, descriptions of discharge (color, odor, settled or suspended solids, oil sheen, or other obvious indicators of pollution), and specific location of discharge location;
- G. Any amendments to the Permit as a result of inspections must be documented within seven calendar days as described in the
- A. Nonfunctional BMPs must be repaired or replaced by the end of the next business day after discovery unless a different time frame is indicated.
- B. Follow the designer's or manufacturer's recommended maintenance procedures for all BMPs.
- Remove sediment from BMPs when the depth of sediment has reached 1/2 the height of the BMP and properly dispose of sediment into controlled areas to prevent soil from returning to the BMP during subsequent rain events. Remove sediment from paved roadways within one calendar day of discovery.
- Remove sediment from around BMPs protecting storm drain inlets. F. Surface waters with evidence of sediment deposition must be stabilized and sediment removed within seven calendar days of discovery, or as stated by the Permit.
- G. Ensure that construction support activities, including borrow areas, waste areas, contractor work areas, and material storage areas and dedicated concrete and asphalt batch plants are cleaned and maintained. H. Replace damaged BMPs that no longer operate effectively.
- Add BMPs as needed during construction to minimize erosion and prevent sediment from leaving the site.

# RECORD KEEPING / RECORD RETENTION

- 1. The SWPPP (original or copies), including all changes to it, and inspections and maintenance records, shall be kept at the site during construction by the Owner / Operator who has operational control of that portion of the site. The SWPPP can be kept in either the field office or in an on site vehicle during normal working hours.
- 2. All Owners(s) must keep the SWPPP, along with the following additional records, on file for three (3) years after submittal of the Notice of Termination (NOT). This does not include any records after submittal of the NOT
- 3. The following is a list of records that shall be kept at the project site available for inspectors to review:
- Copy of the SWPPP, with any modifications:
- Inspection and maintenance records;
- Permanent operation and maintenance agreements;
- Calculations for the design of temporary and permanent stormwater management systems;
- Any other permits required for the project;
- All permanent operation and maintenance agreements that have been implemented, including all right-of-way, contracts, covenants and other binding requirements regarding perpetual maintenance

## LOG OF CHANGES TO THE SWPPP / AMENDMENTS

Records of all inspection and maintenance conducted during construction; and

modified BMPs, designed to correct problems identified or address situations as detailed in the Permit.

#### 1. The Owner / Operator(s) must ensure final stabilization of the site. Final stabilization includes: Ensuring all areas have permanent cover. Vegetative areas must have perennial cover with a density of 70% of expected final growth.

FINAL STABILIZATION

1. The Owner / Operator(s) must amend the SWPPP as necessary to include additional requirements, such as additional or

TERMINATION OF COVERAGE Owner / Operator(s) wishing to terminate coverage under the Permit must submit a Notice of Termination (NOT) to the

MPCA. Compliance with the Permit is required until a NOT is submitted. Refer to the Permit for details. Conditions for submitting a NOT include: A. Site must have achieved final stabilization (refer to section above).

The permanent stormwater treatment and conveyance systems must be clean and all accumulated sediment removed. All temporary synthetic erosion prevention and sediment control BMPs must be removed from the site and disposed of

DEVELOPER ST. LOUIS PARK, MN TEL (952)258-8800 - FAX (952) 258-8900

MUNICIPALITY



15 NOV 2022 11 JAN 2023 08 MAR 2023 30 MAY 2023 CITY SUBMITTAL
PERMIT SET
CITY / WATERSHED RESUBMITTAL

IF THE SIGNATURE, SEAL OR FOUR LINES DIRECTLY ABOVE ARE NOT VISIBLE, THIS SHEET HAS BEEN REPRODUCED BEYOND INTENDE READABILITY AND IS NO LONGER A VALID DOCUMENT. PLEASE CONTAC'
THE ENGINEER TO REQUEST ADDITIONAL DOCUMENTS. CITY / WATERSHED RESUBMITTAL

License No. 47165

CERTIFICATION

I hereby certify that this plan was prepared by me, or under my direct supervision, and that I am

Signature shown is a digital reproduction of original. Wet signed copy of this plan on file at Landform Professional Services, LLC office and is available upon request.

Minneapolis, MN 55401 Web: landform.net PROJECT NO.

MN SWPPP NOTES

C3.2

Know what's **Below**. **Call** before you dig.



**GENERAL NOTES** 

1. For construction staking and surveying services contact Landform at 612.252.9070.

## UTILITY NOTES

PVC Schedule 40 (ASTM: D1785, D2665, F794, & F1866) Storm Sewer

RCP 12"-18" Class 5 (ASTM C76) Drain Tile HDPE - Corrugated & Perforated (ASTM F405 & F667)

3. Contact utility service providers for field location of services 72 hours prior to beginning.

4. Contractor to field verify location and elevation of all utility points of connection prior to construction of any proposed utilities. Contractor to notify Engineer immediately if there is any discrepancy.

5. Contractor to pothole all utility crossings prior to construction of new utilities to verify depths of existing lines. Contact Engineer immediately if any conflicts are discovered.

6. Provide means and measures to protect adjacent property from damage during utility installation.

7. Pipe lengths shown are from center of structure to center of structure or end of end section.

8. Install tracer wire with all non-conductive utilities in accordance with City of Bloomington Standards.

9. Connect to City utilities in accordance with City of Bloomington Standards.

10. HDPE pipe connections into all concrete structures must be made with water tight materials utilizing an A-Lok or WaterStop gasket or boot, cast-in-place rubber boot, or approved equal. Where the alignment precludes the use of the above approved watertight

11. Utility permits are required for connection to the public storm, sanitary, and water system. Contact utilities (952-563-8777) for permit

12. Deflect water to maintain 18-inch minimum outside separation at sewer crossings. Center pipe lengths to provide greatest separation

methods, Conseal 231 WaterStop sealant, or approved equal will only be allowed as approved by the Engineer.

13. Contact City of Bloomington Utilities Department Department, at 952.563.8777 for flushing and pressure test inspections.

Reserved.

17. All portions of the storm sewer system, located within 10 feet of the building or water service line must be tested in accordance with Minnesota Rules, Part 4714.

18. All joints and connections in the storm sewer system shall be gastight or water tight. Approved resilient rubber joints must be used to

make watertight connections to manholes, catch basins, and other structures.

19. Catch basins in curb and gutter are sumped 2 inches below the gutter grade.

20. Rock media in infiltration or filtration systems shall be angular, non-calcareous rock.

21. Irrigation sleeve to be 4 inch Schedule 80 PVC buried 24" below grade. Extend sleeves 3-feet beyond the edge of pavement. Mark each end of sleeve with 3/4-inch rebar 12 inches below finish grade. (Coordinate with irrigation contractor.)

22. Coordinate with Private Utilities to provide electric, natural gas, and communications services to building.

23. The primary electric feed, transformer, and meter are provided and installed by Xcel Energy. The transformer pad design is provided by the Utility and construction is by the Contractor. Contact Utility for pad detail. The secondary electric and conduits shall be installed by the Electrical Contractor.

24. See site lighting plan for additional information.

25. Protect sanitary service line. Contractor to inspect line after construction to ensure it has not been damaged.

27. Provide conduits for cable television and other electronic communication.

28. Coordinate with Mechanical, Plumbing, and Electrical Drawings for locations of service connections and continuation of services

29. Compact cohesive soils in paved areas to 95% of maximum dry density, Standard Proctor (ASTM D698) except the top 3 feet which shall be compacted to 100%. compact to 98% density where fill depth exceeds 10 feet. The soils shall be within 3% of optimum moisture content. In granular soils all portions of the embankment shall be compacted to not less than 95% of Modified Proctor

30. Adjust structures to final grade where disturbed. Comply with requirements of Utility. Meet requirements for traffic loading in paved

INFILTRATION / FILTRATION BASIN REQUIREMENTS

UTILITY CROSSINGS

Crossing 1
Storm Sewer Bottom=835.02 Sanitary Sewer Top=832.47 Clearance = 2.55'

I hereby certify that this plan was prepared by me, or under my direct supervision, and that I am

CERTIFICATION

DEVELOPER

3701 ALABAMA AVENUE SOUTH

ST. LOUIS PARK, MN TEL (952)258-8800 - FAX (952) 258-8900

**MUNICIPALITY** 

BLOOMINGTON

LUTHER

BLOOMINGTON, MN

DRC SUBMITTAL CITY SUBMITTAL PERMIT SET CITY / WATERSHED RESUBMITTAL

15 NOV 2022 11 JAN 2023 08 MAR 2023 30 MAY 2023

License No. 47165 Signature shown is a digital reproduction of original. Wet signed copy of this plan on file at Landform Professional Services, LLC office and is available upon request.

IF THE SIGNATURE, SEAL OR FOUR LINES DIRECTLY ABOVE ARE NOT VISIBLE, THIS SHEET HAS BEEN REPRODUCED BEYOND INTENDED READABILITY AND IS NO LONGER A VALID DOCUMENT. PLEASE CONTACT THE ENGINEER TO REQUEST ADDITIONAL DOCUMENTS.

CITY / WATERSHED RESUBMITTA



105 South Fifth Avenue Tel: 612-252-9070 FILE NAME PROJECT NO.

Minneapolis, MN 55401 Web: landform.net C401LUT22054.DWG UTILITIES

Land form @ and Site to Finish @ are registered service marks of Land form Professional Services, LLC.



MATERIAL LOCATION		DESCRIPTION	AASHTO MATERIAL CLASSIFICATIONS	COMPACTION / DENSITY REQUIREMENT
D	FINAL FILL: FILL MATERIAL FOR LAYER 'D' STARTS FROM THE TOP OF THE 'C' LAYER TO THE BOTTOM OF FLEXIBLE PAVEMENT OR UNPAVED FINISHED GRADE ABOVE. NOTE THAT PAVEMENT SUBBASE MAY BE PART OF THE 'D' LAYER	ANY SOIL/ROCK MATERIALS, NATIVE SOILS, OR PER ENGINEER'S PLANS. CHECK PLANS FOR PAVEMENT SUBGRADE REQUIREMENTS.	N/A	PREPARE PER SITE DESIGN ENGINEER'S PLANS. PAVED INSTALLATIONS MAY HAVE STRINGENT MATERIAL AND PREPARATION REQUIREMENTS.
С	INITIAL FILL: FILL MATERIAL FOR LAYER 'C' STARTS FROM THE TOP OF THE EMBEDMENT STONE ('B' LAYER) TO 24" (600 mm) ABOVE THE TOP OF THE CHAMBER. NOTE THAT PAVEMENT SUBBASE MAY BE A PART OF THE 'C' LAYER.	GRANULAR WELL-GRADED SOIL/AGGREGATE MIXTURES, <35% FINES OR PROCESSED AGGREGATE.  MOST PAVEMENT SUBBASE MATERIALS CAN BE USED IN LIEU OF THIS LAYER.	AASHTO M145 <sup>1</sup> A-1, A-2-4, A-3  OR  AASHTO M43 <sup>1</sup> 3, 357, 4, 467, 5, 56, 57, 6, 67, 68, 7, 78, 8, 89, 9,	BEGIN COMPACTIONS AFTER 24" (600 mm) OF MATERIAL OVER THE CHAMBERS IS REACHED. COMPACT ADDITIONAL LAYERS IN 12" (300 mm) MAX LIFTS TO A MIN. 95% PROCTOR DENSITY FOR WELL GRADED MATERIAL AND 95% RELATIVE DENSITY FOR PROCESSED AGGREGATE MATERIALS.
В	<b>EMBEDMENT STONE</b> : FILL SURROUNDING THE CHAMBERS FROM THE FOUNDATION STONE ('A' LAYER) TO THE 'C' LAYER ABOVE.	CLEAN, CRUSHED, ANGULAR STONE	AASHTO M43 <sup>1</sup> 3, 4	NO COMPACTION REQUIRED.
Α	FOUNDATION STONE: FILL BELOW CHAMBERS FROM THE SUBGRADE UP TO THE FOOT (BOTTOM) OF THE CHAMBER.	CLEAN, CRUSHED, ANGULAR STONE	AASHTO M43 <sup>1</sup> 3, 4	PLATE COMPACT OR ROLL TO ACHIEVE A FLAT SURFACE. 2,3
	PERIMETER STONE (SEE NOTE 4)		"TO BOTTOM OF FLEXIBLE PAVEMENT. FOR UNPAVED ALLATIONS WHERE RUTTING FROM VEHICLES MAY OCCUR. INCREASE COVER TO 24" (600 mm).	8' 18" (450 mm) (2.4 m) MIN* MAX 12" (300 mm) MIN
PACTION	I REQUIREMENTS. 'C' IS PLACED, ANY SOIL/MATERIAL CAN BE PLACED IN LAYER 'D' UP T	TANDARD DESIGN LOAD CONDITIONS, A FLAT SURFACE MAY BE ACHIEVED BY O THE FINISHED GRADE. MOST PAVEMENT SUBBASE SOILS CAN BE USED TO F I NON-WOVEN GEOTEXTILE ALL GULAR STONE IN A & B LAYERS		,
,	EXCAVATION WALL (CAN BE SLOPED OR VERTICAL)  6" (150 mm) MIN	B		TWIN 4
		END CAP SUBGRADE SOILS (150 mm) N (SEE NOTE 3)	77" (1956 mm)	12" (300 mm) MIN
MBER CL	ASSIFICATION 45x76 DESIGNATION SS.	*FOR COVER DEPTHS GREATER THAN 8.0' (2.4 m) PLEA ICATION FOR POLYPROPYLENE (PP) CORRUGATED WALL STORMWATER COLL NDARD PRACTICE FOR STRUCTURAL DESIGN OF THERMOPLASTIC CORRUGAT	ECTION CHAMBERS"	RS"
SITE DES THE RAN RIMETER S QUIREMEN TO MAII	SIGN ENGINEER IS RESPONSIBLE FOR ASSESSING THE BEARING RESI IGE OF EXPECTED SOIL MOISTURE CONDITIONS. STONE MUST BE EXTENDED HORIZONTALLY TO THE EXCAVATION WAL ITS FOR HANDLING AND INSTALLATION: NTAIN THE WIDTH OF CHAMBERS DURING SHIPPING AND HANDLING, O FURE A SECURE JOINT DURING INSTALLATION AND BACKFILL, THE HEI	STANCE (ALLOWABLE BEARING CAPACITY) OF THE SUBGRADE SOILS AND THE  L FOR BOTH VERTICAL AND SLOPED EXCAVATION WALLS.  CHAMBERS SHALL HAVE INTEGRAL, INTERLOCKING STACKING LUGS.	DEPTH OF FOUNDATION STONE WITH CONSIDI	ERATION


UNDERGROUND INFILTRATION SYSTEM

NO SCALE









CERTIFICATION

I hereby certify that this plan was prepared by me, or under my direct supervision, and that I am a duly Licensed Professional Engineer under the laws of the state of MINNESOTA.

Steven E. Sabraski
License No. 47165

Date: 05/30/2023

Signature shown is a digital reproduction of original. Wet signed copy of this plan on file at Landform Professional Services, LLC office and is available upon request.

IF THE SIGNATURE, SEAL OR FOUR LINES DIRECTLY ABOVE ARE NOT VISIBLE, THIS SHEET HAS BEEN REPRODUCED BEYOND INTENDED READABILITY AND IS NO LONGER A VALID DOCUMENT. PLEASE CONTACT THE ENGINEER TO REQUEST ADDITIONAL DOCUMENTS.

CITY / WATERSHED RESUBMITTAL MAY 30, 2023

L A N D F O

From Site to Finish

105 South Fifth Avenue Tel: 612-2
Suite 513 Fax: 612-2

 105 South Fifth Avenue
 Tel: 612-252-9070

 Suite 513
 Fax: 612-252-9077

 Minneapolis, MN 55401
 Web: landform.net

 FILE NAME
 C701LUT22054.DWG

 PROJECT NO.
 LUT22054

civil construction details C7.2

Landform®and Site to Finish®are registered service marks of Landform Professional Services, LLC.